

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE


Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of work: Estimate for Construction of RCC Drains at Agrahara Layout in Ward No.05, Byatarayanapura Sub Division


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1187.52	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, P. No. 5/ Item No. 2.1/ PWD SR 2014-15	cum	146.88	Rupees One Hundred Forty Six And Paise Eighty Eight Only
2	6058.80	Removing B.S Slab of Drain and stacking Page No. 28/ Item No. 5.32/ PWD SR 2014-15	Sqm	58.32	Rupees Fifty Eight And Paise Thirty Two Only
3	6058.80	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 28/ Item No. 5.33/ PWD SR 2014-15	Sqm	75.60	Rupees Seventy Five And Paise Sixty Only
4	2019.60	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete - do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2014-15	Sqm	639.36	Rupees Six Hundred Thirty Nine And Paise Thirty Six Only
5	1436.16	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	264.60	Rupees Two Hundred Sixty Four And Paise Sixty Only
6	718.08	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2, No. 12/ Item No. 4.3/ PWD SR 2014-15	Cum	4847.04	Rupees Four Thousand Eight Hundred Forty Seven And Paise Four Only
7	5785.60	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 27/ Item No. 5.27/ PWD SR 2014-15	Sqm	993.60	Rupees Nine Hundred Ninety Three And Paise Sixty Only
8	502.72	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:2:4 with OPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2/P No. 13/ Item No. 4.6/ PWD SR 2014-15	cum	5327.64	Rupees Five Thousand Three Hundred Twenty Seven And Paise Sixty Four Only


EXECUTIVE ENGINEER-
KRIDL, BBMP, Bangalore



Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
9	6615.00	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shuttering machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Material (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1856.67	Rupees One Thousand Eight Hundred Fifty Six And Paise Sixty Seven Only
10	2623.68	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	67.32	Rupees Sixty Seven And Paise Thirty Two Only


EXECUTIVE ENGINEER-2
KRIDL, BBMP, Bangalore


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92